

CITY OF MORENO VALLEY

PUBLIC WORKS DEPARTMENT

QUALITY ASSURANCE PROGRAM (QAP)



Revised: October 1, 2010

Prepared By: Guy Pegan, Senior Engineer, P.E.
Capital Projects Division
Public Works Department
City of Moreno Valley
14177 Frederick Street
Moreno Valley, CA 92553

QUALITY ASSURANCE PROGRAM (QAP)

CITY OF MORENO VALLEY

The purpose of this program is to provide assurance that the materials incorporated into the construction projects are in conformance with the contract specifications. This program is in conjunction with the Caltrans documents “Quality Assurance Program Manual for Use by Local Agencies” and “Local Assistance Procedures Manual” Section 16.14 Quality Assurance Program for off the National Highway System (NHS) and off the State Highway System (SHS). For on the National Highway System (NHS) and on the State Highway System (SHS) detail QAP requirements refer to the Caltrans “Local Assistance Procedures Manual” Section 16.14 Quality Assurance Program. This program will be updated every five years or more frequent if there are changes of the testing frequencies or to the tests themselves.

INTRODUCTION

A Quality Assurance Program (QAP) consists of an Acceptance Program and an Independent Assurance (IA) Program that will provide assurance that the materials and workmanship incorporated into a construction project are in conformance with the contract specifications for off the National Highway System and off the State Highway System. To accomplish the Local Agency QAP requirements by Caltrans, the following terms, definitions, and procedures will be used:

DEFINITION OF TERMS

- Acceptance Testing (AT) – Sampling and testing, or inspection, to determine the degree of compliance with contract requirements.
- Independent Assurance (IA) Program (IAP) – Verification that AT is being performed correctly by qualified testers and laboratories.
- Quality Assurance Program (QAP) – A sampling and testing program that will provide assurance that the materials and workmanship incorporated into the construction project are in conformance with the contract specifications. The main elements of a QAP are the AT, and IAP.
- Source Inspection – AT of manufactured and prefabricated materials at locations other than the job site, generally at the manufactured location.
- Caltrans Materials Engineering and Testing Services (MET) – Performs IA services for local agencies with Federal-aid projects off the NHS.
- Witness Test: IA person meets with the local agency acceptance sampler and tester, and observes the person performing the test (or tests) that the person is qualified to perform.
- Proficiency Test: At least once during each calendar year, the IA person should conduct a confirmation test of each Acceptance Tester, with a representative sample of soil or aggregate, to verify that the AT tester is proficient in performing the applicable test.

MATERIALS LABORATORY

The City of Moreno Valley will use private consultant materials laboratory to perform AT on Federal-aid and other designated projects. The materials laboratory shall be under the responsible

management of a California registered Engineer with experience in sampling, inspection and testing of construction materials. The Engineer shall certify the results of all tests performed by laboratory personnel under the Engineer's supervision. The materials laboratory shall contain certified test equipment capable of performing the tests conforming to the provisions of this QAP.

The materials laboratory used shall provide documentation that the laboratory complies with the following procedures:

1. Correlation Testing Program – The materials laboratory shall be a participant in one or more of the following testing programs:
 - a. AASHTO Materials Reference Laboratory (AMRL)
 - b. Cement and Concrete Reference Laboratory (CCRL)
 - c. Caltrans' Reference Samples Program (RSP)
2. Certification of Personnel – The materials laboratory shall employ personnel who are certified by one or more of the following:
 - a. Caltrans District Materials Engineer
 - b. Nationally recognized non-Caltrans organizations such as the American Concrete Institute, Asphalt, National Institute of Certification of Engineering Technologies, etc.
 - c. Other recognized organizations approved by the State of California and/or recognized by local governments or private associations.
3. Laboratory and Testing Equipment – The materials laboratory shall only use laboratory and testing equipment that is in good working order. All such equipment shall be calibrated at least once each year. All testing equipment must be calibrated by impartial means using devices of accuracy traceable to the National Institute of Standards and Technology. A decal shall be firmly affixed to each piece of equipment showing the date of the last calibration. All testing equipment calibration decals shall be checked as part of the IAP.

ACCEPTANCE TESTING (AT)

AT will be performed by a materials laboratory certified to perform the required tests. The tests results will be used to ensure that all materials incorporated into the project are in compliance with the contract specifications.

Testing methods will be in accordance with the California Test (CT) Methods or a national recognized standard (i.e., AASHTO, ASTM, NIST, etc.) as specified in the contract specifications. **On all Federal-aid projects, the testers shall use the California Test Methods.**

Sample locations and frequencies may be in accordance with the contract specifications. If not so specified in the contract specifications, samples shall be taken at the locations and frequencies as shown in Attachment #1 (Appendix D, "Acceptance Sampling and Testing Frequencies" of the Caltran's QAP Manual).

AT will generally be required to perform the following on all projects:

The Consultant shall perform public works geotechnical inspection and materials testing services for this project to include, but not be limited to, the following:

- Expertise in geotechnical matters related to storm drain and roadway construction and grading, and knowledge of the local area soils and geology, City's past practices and generally accepted industry standards for work associated with the type of project.
- Safe and proper use of Nuclear Gauge for compaction testing.
- Proper procedures and protocols for field sampling and testing of graded earth materials, backfill materials, sub-grade, base, AC and PCC.
- Ability to provide field test results immediately to the City's Project Inspector and Engineer, and laboratory test results within 48-hours, unless test procedures and protocols require longer.
- Review of contractor material submittals, sample/test frequency protocols, and criteria for acceptable results and provision of materials and compaction reports.

Office Activities:

1. Review and thoroughly understand all contract documents, including construction drawings, specifications, and referenced testing methods and protocols.
2. Review and thoroughly understand geotechnical and soils reports, materials testing lab reports, contractor submitted mix reports, and other like documentation.
3. Review and thoroughly understand project schedules and related sampling, testing, and submittal requirements (field sampling and testing, compliance certificates, materials samples, etc.) from the contractor for conformance to the plans and specifications.
4. Participate in pre-construction meetings, field meetings, construction progress meetings, final walk-through meetings, as-built plan completion meetings, equal opportunity meetings, and other administrative meetings as necessary.
5. Monitor and report on the Contractor's extra work as it relates to geotechnical sampling, testing and reporting, field and laboratory materials testing.
6. Assist in the negotiation of change orders as they relate to geotechnical sampling, testing, and reporting, as requested by the City.
7. Review all unknown, unforeseen, and changed conditions that occur, and all disputed work claims from the Contractor as it relates to geotechnical responsibilities and field-testing, and recommend a course of action to the Engineer.
8. Prepare and maintain all geotechnical files, daily inspection records, including site photographs, project status reports, and all geotechnical inspection and testing records as they relate to earthwork materials testing and compaction testing.
9. Prepare and maintain records of geotechnical work requested and completed, geotechnical related computer files, daily geotechnical field work (when on-site), geotechnical inspections, samples and test records, field and laboratory test results, and all geotechnical related records and files.
10. Provide labor compliance reports and certified payroll of the Consultant's fieldwork.

Field Activities:

1. Coordinate with the Contractor, City personnel, and other consultants on the job site as needed.
2. Coordinate ongoing geotechnical field and laboratory testing, as required, including reviewing and monitoring the Contractor's requests for re-testing.
3. Conduct on-demand field geotechnical inspections for quality of materials and installation and workmanship, including quality, placement, and compaction of earthen materials, for conformance to plans and specifications pursuant to all applicable City codes, ordinances, and directives.
4. Keep daily (when on-site) geotechnical field notes and take photographs of the field sampling and geotechnical inspection work, including photographic evidence of non-complying materials or work. A daily report identifying work done by the geotechnical technician, including photographs, shall be submitted to the Project Inspector by the next business day for review and filing.
5. During the course of fieldwork, if the Consultant geotechnical personnel observe an unsafe situation, he/she shall immediately advise the Contractor's nearest available personnel and notify the City's Inspector and the Engineer.

General:

1. Participate with the City in meetings with contractors, public utility agencies, and other government agency representatives as requested.

INDEPENDENT ASSURANCE PROGRAM (IAP)

"REQUIRED FOR ALL FEDERAL PROJECTS"

IAP shall be provided by personnel from Caltrans, or the City's consultant certified materials laboratory. IAP will be used to verify that sampling and testing procedures are being performed properly and that all testing equipment is in good condition and properly calibrated.

IAP personnel shall be certified in all required testing procedures, as part of IAP, and shall not be involved in any aspect of AT.

IAP should be performed on materials test required for the project as identified by the agency or as required by FHWA requirements for the project. Proficiency tests should be performed on Sieve Analysis, Sand Equivalent, and/or Cleanness Value tests. All other types of IAP should be witness tests. **On all Federal-aid projects, the testers shall use the California Test Methods.**

Poor correlation between acceptance tester's results and other test results may indicate probable deficiencies with the acceptance sampling and testing procedures. In cases of unresolved discrepancies, a complete review of AT shall be performed by IAP personnel, or an independent materials laboratory chosen by the Agency. IAP samples and tests are not to be used for determining compliance with contract requirements. Compliance with contract requirements is determined only by AT. On all Federal-aid Projects, Caltrans (MET) will perform IA services, and the testers shall use California Test Methods.

REPORTING ACCEPTANCE TESTING RESULTS

The following are time periods for reporting material test results to the Resident Engineer:

- When the aggregate is sampled at material plants, test results for Sieve Analysis, Sand Equivalent and Cleanness Value should be submitted to the Resident Engineer within 24 hours after sampling.
- When materials are sampled at the job site, test results for compaction and maximum density should be submitted to the Resident Engineer within 24 hours after sampling.
- When soils and aggregates are sampled at the job site:
 - (1) Test results for Sieve Analysis, Sand Equivalent, and Cleanness Value should be submitted to the Resident Engineer within 72 hours after sampling.
 - (2) Test results for “R” Value and asphalt concrete extraction should be submitted to the Resident Engineer within 96 hours after sampling.

When sampling products such as Portland Cement Concrete (PCC), cement-treated base (CTB), hot mix asphalt (HMA), and other such materials; the time of such sampling shall be varied with respect to the time of the day insofar as possible, in order to avoid a predictable sampling routine. The reporting of AT results, if not performed by the Resident Engineer’s staff, shall be done on an expedited basis such as by fax or telephone.

TESTING OF MANUFACTURED MATERIALS

During the Design phase of the project, the Project Engineer may submit a “Source Inspection Request” see Attachment #2 (Exhibit 16-V of the Caltran’s LAPM) to the consultant, or Caltrans for inspection and testing of manufactured and prefabricated materials by their materials laboratory. A list of materials that can be typically accepted on the basis of certificates of compliance during construction is found in Attachment #3 (Appendix F of the Caltran’s QAP Manual). All certificates of compliance shall conform to the requirements of the contract specifications, for examples see Attachment #4 (Appendix J of the Caltran’s QAP Manual).

Should the City request Caltrans to conduct the source inspection, and the request is accepted, all sampling, testing, and acceptance of manufactured and prefabricated materials will be performed by Caltrans’ Office of Materials Engineering and Testing Services.

For Federal-aid projects on the National Highway System (NHS), Caltrans will assist in certifying the materials laboratory, and the acceptance samplers and testers. For Federal-aid projects off the NHS, Caltrans may be able to assist in certifying the materials laboratory, and the acceptance samplers and testers.

PROJECT CERTIFICATION

Upon completion of a Federal-aid project, a “Materials Certificate” shall be completed by the Resident Engineer. The City shall include a “Materials Certificate” in the Report of Expenditures submitted to the Caltrans District Director, Attention: District Local Assistance Engineer. A copy of the “Materials Certificate” shall also be included in the City’s construction records. The Resident Engineer in charge of the construction function for the City shall sign the certificate. All materials incorporated into the work that did not conform to specifications must be explained and justified on the “Materials

Certification”, including changes by virtue of contract change orders. See Attachment #5 (Appendix K of the Caltran’s QAP Manual) for an example.

RECORDS


All material records of samples and tests, material releases and certificates of compliance for the construction project shall be incorporated into the Resident Engineer’s project file. If a Federal-aid project:

- The files shall be organized as described in Section 16.8 “Project Files” of the Caltran’s Local Assistance Procedures Manual.
- It is recommended that the complete project file be available at a single location for inspection by Caltrans and Federal Highway Administration (FHWA) personnel.
- The project files shall be available for at least three years following the date of final project voucher.
- The use of a “Log Summary,” as shown in Attachment # 6, Appendix H of the Caltran’s QAP Manual, facilitates reviews of material sampling and testing by Caltrans and FHWA, and assists the Resident Engineer in tracking the frequency of testing.

When two or more projects are being furnished identical materials simultaneously from the same plant, it is not necessary to take separate samples or perform separate tests for each project; however, copies of the test reports are to be provided for each of the projects to complete the records.

This City of Moreno Valley Quality Assurance Program document supersedes other herein reference Quality Assurance Programs for off the National Highway System (NHS) and off the State Highway System (SHS) projects.

APPROVED BY: _____


Chris A. Vogt,
Public Works Director/City Engineer
R.C.E 44250 Exp. 6/30/2011



Appendix D - Acceptance Sampling and Testing Frequencies

Note: It may be desirable to sample and store some materials. If warranted, testing can be performed at a later date.

Portland Cement (Hydraulic Cement)

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Cement/fly ash (Sampling only)	8-lb. sample	If possible, take a least one sample per job, even if the material is accepted based on a Certificate of Compliance.	ASTM D75, C494 CT 125 AASHTO T127, M85, M295	Standard for sampling hydraulic cement or fly ash.
Cement (Testing Only)	8-lb. sample	If the product is accepted based on a Certificate of Compliance, testing is not required. If the product is not accepted using a Certificate of Compliance, test at least once per job.	ASTM C109 CT 515 AASHTO T106	If testing appears warranted, fabricate six 2-in. mortar cubes using the Portland (or hydraulic cement). Test for compressive strength.

Portland Cement Concrete (Hydraulic Cement Concrete)

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Aggregate for Hydraulic Cement Concrete (Sampling & Testing)	50-lb. sample	Take one aggregate sample for each 1000 cu. yd. of PCC/HCC concrete. Test at least one sample per job.	ASTM D75 CT 125 AASHTO M6, T2, M80	Sample aggregate from belt or hopper (random basis).
Water (Sampling & Testing)	Take a two-quart sample using a clean plastic jug (with lining) and sealed lid. Sample at the point of use.	If the water is clean with no record of chlorides or sulfates greater than 1%, no testing is required. If the water is dirty do not use it. Test only when the chloride or sulfates are suspected to be greater than 1%.	CT 405, CT 422, CT 417 AASHTO R23	If testing appears warranted, test for chlorides and sulfates.



Appendix D (continued)

Portland Cement Concrete (Hydraulic Cement Concrete) – Continued

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description of Comments
Air Entraining Admixtures (Sampling & Testing)	Take a one-quart sample using a clean, lined can or plastic bottle, if liquid. If powder, take a 2.5 lb. sample.	If the product is accepted based on a Certificate of Compliance, testing is not required. Take one sample per job. Prior to sampling, check with Caltrans (METS) for acceptable brands and dosage rates.	ASTM C233 AASHTO M154, T157, C260	If testing appears warranted, test for sulfates and chlorides Admixtures with sulfates and chlorides greater than 1% should not be used.
Water Reducers or Set Retarders (Sampling & Testing)	If liquid, take a 1-qt. sample using a clean plastic can. If powder, take a 2.5 lb. sample.	If the product is accepted based on a Certificate of Compliance, no testing is required. If not, test once per job. Prior to using this product, please check with Caltrans (METS) for acceptable brands and dosage rates.	ASTM C494 AASHTO M194	If testing appears warranted, test for sulfates and chlorides. Admixtures with sulfates and chlorides greater than 1% should not be used.
Freshly-Mixed Concrete (Sampling)	Approx. 150lb. (or 1 cu. ft.) near mixer discharge.	When tests are required, take at least one sample for each 500 to 1000 cu. yd. of PCC/HCC.	ASTM C172, C685 CT 539 AASHTO T141, M157	This describes a method to sample freshly-mixed concrete.
Freshly-Mixed Concrete (Testing)	Approx. 150 lb/ (or 1 cu. ft.) near mixer discharge.	On projects with 500 cu. yd., or more, test at least one sample per job.	ASTM C143 AASHTO T119	This test determines the slump of the freshly-mixed concrete.
Freshly-Mixed Concrete (Testing)	Approx. 150 lb/ (or 1 cu. ft.) near mixer discharge	On projects with 500 cu. yd., or more, test at least one sample per job.	ASTM C360 CT 533	This test determines the ball penetration of the freshly-mixed concrete.
Freshly-Mixed Concrete (Testing)	Approx. 150 lb/ (or 1 cu. ft.) near mixer discharge	On projects with 500 cu. yd., or more, test at least one sample per job.	ASTM C231 CT 504 AASHTO T152	This test determines the air content of freshly-mixed concrete (pressure method).
Freshly-Mixed Concrete (Testing)	Approx. 150 lb/ (or 1 cu. ft.) near mixer discharge	On projects with 500 cu. yd., or more, test at least one sample per job.	ASTM C138 CT 518 AASHTO T121	This test determines the unit weight of freshly mixed concrete.



Appendix D (continued)

Portland Cement Concrete (Hydraulic Cement Concrete) – Continued

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Freshly-Mixed Concrete (Testing)	Approx. 150 lb/ (or 1 cu. ft.) near mixer discharge	Fabricate at least two concrete cylinders per project. Test for compressive strength at least once for each 500 to 1,000 cu. yd. of structural concrete.	ASTM C39 CT 521 AASHTO T22	This test is used to fabricate 6" x 12" concrete cylinders. Compressive strengths are determined, when needed.
Freshly-Mixed Concrete (Testing)	Approximately 210 lb. of concrete are needed to fabricate three concrete beams.	One sample set for every 500 to 1,000 cu. yd. of concrete.	ASTM C78 CT 31 AASHTO T97 & T23	This test is used to determine the flexural strength of simple concrete beams in third-point loading

Soils and Aggregates

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Aggregate (Sampling)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM D75 CT 125 AASHTO T2	This test describes the procedures to sample aggregate from the belt or hopper (random basis).
Fine Aggregates (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM C128 CT 208 AASHTO T84	This test determines the apparent specific gravity of fine aggregates for bituminous mixes, cement treated bases and aggregate bases.
Fine Aggregate (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM C128 CT 207 AASHTO T84	This test determines the bulk specific gravity (SSD) and the absorption of material passing the No. 4 sieve.
Coarse Aggregate (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	CT 206	This test determines the cleanness of coarse aggregate.



Appendix D (continued)

Soils and Aggregates - Continued

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Coarse Aggregate (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM C127 CT 227 AASHTO T85	This test determines the specific gravity and absorption of coarse aggregate (material retained on the No. 4 sieve).
Soils and Aggregates (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM C136 CT 202 AASHTO T27	This test determines the gradation of soils and aggregates by sieve analysis.
Soils and Aggregates (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM D2419 CT 217 AASHTO T176	This test determines the Sand Equivalent of soils and aggregates.
Soils and Aggregates (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM C117 AASHTO T11	This test determines the gradation for materials finer than the No. 200 sieve (by washing method).
Soils and Aggregates (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM D3744 CT 229 AASHTO T210	This test determines the Durability Index of soils and aggregates.
Soils and Aggregates (Testing)	One 50-lb. sample	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM D2844 CT 301 AASHTO T190	This test determines the Resistance Value (R-) and expansion pressure of compacted materials.
Soils and Aggregates (Testing)	One random location for every 2,500 sq. ft.	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM D2922 CT 231 AASHTO T238	This test determines field densities using the nuclear gage.
Soils and Aggregates (Testing)	One random location for every 2,500 sq. ft.	Take one sample for every 500 to 1,000 tons of materials. Test at least one sample per project.	ASTM D3017 CT 231 AASHTO T239	This test determines the water content using the nuclear gage.



Appendix D (continued)

Asphalt Binder

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Asphalt Binder (Sampling)	One 0.5-gal. sample placed in a clean, sealed can.	Sample once per job at the asphalt concrete plant.	CT 125 ASTM D 979 AASHTO T 168, T48	This procedure describes the proper method to sample the asphalt binder.
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Sample once per job at the asphalt concrete plant.	ASTM D92, D117 AASHTO T 48	This test determines the flash point of the asphalt binder (by Cleveland open cup).
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D2872 & D92 CT 346 AASHTO T240 & T48	This test determines the rolling thin-film oven test (RTFO).
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D2042 AASHTO T44	This test determines the solubility of asphalt material in trichloroethylene.
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D2171 AASHTO T202	This test determines the dynamic viscosity, (absolute viscosity of asphalt @ 140 degrees F by the Vacuum Capillary Viscometer Poises).
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D5 AASHTO T49	This test determines the penetration of bituminous material @ 77 degrees F and percentage of original penetration from the residue.
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D113 AASHTO T51	This test determines the ductility of asphalt @ 77 degrees F.
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D2170 AASHTO T201	This test determines the kinematic viscosity of asphalt @275 degrees F (Centistoke).



Appendix D (continued)

Asphalt Binder - Continued

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D2171 AASHTO T202	This test determines the dynamic viscosity. (absolute viscosity of asphalt @ 140 degrees F by the Vacuum Capillary Viscometer Poises).
Asphalt Binder (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D36 AASHTO T53	This test determines the softening point of asphalt.

Asphalt Emulsified

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Emulsified Asphalt (Sampling)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D140, D979 CT 125 AASHTO T 40, T168	This test describes the procedure to sample the emulsified asphalt.
Emulsified Asphalt (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D244 AASHTO T59	This test determines the sieve retention of emulsified asphalt.
Emulsified Asphalt (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D244 AASHTO T59	This test determines the weight per gallon of emulsified asphalt.
Emulsified Asphalt (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D244 AASHTO T59	This test determines the penetration of the emulsified asphalt.
Emulsified Asphalt (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D244 CT 330 AASHTO T59	This test determines the residue @ 325 degrees F evaporation of emulsified asphalt.



Appendix D (continued)

Asphalt Emulsified - Continued

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Emulsified Asphalt (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D4402 AASHTO T201	This test determines the Brookfield viscosity.
Emulsified Asphalt (Testing)	One 0.5-gal. sample placed in a clean, sealed can.	Obtain one sample at the asphalt concrete plant for each 1,000 tons of asphalt concrete placed.	ASTM D88 AASHTO T72	This test determines the Saybolt-Furol viscosity of emulsified asphalt @ 77 degrees F (seconds).

Hot Mix Asphalt (Asphalt Concrete) – Concrete

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Asphalt Concrete (Sampling)	Obtain one 30-lb. sample each day of production	Obtain one sample at the asphalt concrete plant for each 5,000 tons of asphalt concrete placed.	ASTM D75, D140, D979 CT 125 AASHTO T 40, T168	This test describes the procedure to sample the asphalt concrete.
Asphalt Concrete (Testing)	4" x 8" cores	Take one 4" x 8" core for every 500 ft of paved roadway.	ASTM D1188, D1560, D1561, D5361 CT 304 AASHTO T246, T247	This test determines the field density of street samples.
Asphalt Concrete (Testing)	Obtain one 30-lb. sample for each day of production	Obtain one sample for every five cores taken.	ASTM D1188, D1560, D1561, D5361 CT 304 AASHTO T246, T247	This test determines the laboratory density and relative compaction of asphalt concrete.
Asphalt Concrete (Testing)	4" x 8" cores	Obtain one sample for every five cores taken.	ASTM D2726, D1188, D5361	This test determines the specific gravity of compacted bituminous mixture dense-graded or non-absorptive.



Appendix D (continued)

Hot Mix Asphalt (Asphalt Concrete) –Continued

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Asphalt Concrete (Testing)	One 30-lb sample	Obtain one sample for every 1,000 tons of asphalt concrete.	ASTM D1559 AASHTO T245	This test determines the resistance to plastic flow of prepared mixes as determined by the Marshall Method.
Asphalt Concrete (Testing)	One 30-lb sample	Obtain one sample for every 1,000 tons of asphalt concrete.	ASTM C117, D2172 (use Method B) AASHTO T164	This test determines the screen analysis of aggregates recovered from asphalt materials.
Geotextile Fabric (Placed Under the Asphalt Concrete) (Testing)	One 12 ft. x 3 ft. sample	Obtain one sample per job.	ASTM D4632 AASHTO M288	This test determines the weight per sq. yd. and grabs strength of geotextile fabrics.
Asphalt Concrete (Testing)	Sample any test location (random basis)	Obtain one sample for every 1,000 tons of asphalt concrete.	ASTM D2950 CT 375	This test determines the nuclear field density of in-place asphalt concrete.
Asphalt Concrete (Testing)	One 10-lb sample	Obtain one sample during every day of production.	ASTM D1560, D1561 CT 366 AASHTO T246, T247	This test determines the stability value of asphalt concrete.
Slurry Seals (Sample)	One 0.5 gal. sample in a clean, dry plastic container.	Obtain one sample per truck	ASTM D979 CT 125 AASHTO T 40, T168	This test describes the procedure for sampling the slurry seal.
Aggregate for Slurry Seals (Testing)	One 30-lb. sample.	Obtain at least one sample per project from the belt or hopper or stockpile and test for Sand Equivalent	ASTM D2419 CT 217 AASHTO T176	This test determines the Sand Equivalent of aggregates.



Appendix D (continued)

Slurry Seals

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Aggregate for Slurry Seals (Testing)	One 30-lb. sample.	Obtain at least one sample per project from the belt, hopper, or stockpile and test for sieve analysis of fine sand.	ASTM C117 AASHTO T11	This test determines the sieve analysis of fine sand (gradation of materials finer than No. 200 sieve by wash grading).
Slurry Seals (Testing)	One 0.5 gal. sample in a clean, dry plastic container.	Test one sample per project and test for Abrasion.	ASTM D3910	This test determines the Wet Track Abrasion Test (2) (WTAT).

Steel

Materials to be Sampled or Tested	Sample Size	Sampling/Testing Frequency	Typical Test Methods	Description or Comments
Steel Strand (Testing)	Sample strand at various sizes.	This item may be accepted using a Certificate of Compliance. Sample and test at least two steel strands per job when a Certificate of Compliance is not used.	ASTM A370, A416, E328 AASHTO T244	This test determines the tensile strength of uncoated seven-wire stress-relieved strand for pre-stressed concrete.
Steel Rebar (Testing)	Sample rebar at various sizes.	This item may be accepted using a Certificate of Compliance. Sample and test at least two steel rebar per job when a Certificate of Compliance is not used.	ASTM A615, A370 AASHTO T244	This test determines the steel reinforcement bar tensile strength and bend capability.

**SAMPLE COVER MEMO
SOURCE INSPECTION REQUEST
FROM LOCAL AGENCY to
CALTRANS' DISTRICT LOCAL ASSISTANCE ENGINEER
(Prepared By Applicant On Applicant Letterhead)**

To: (name)
Caltrans' District Local Assistance Engineer
Caltrans' Local Assistance Office
(district office address)

Date: _____

Federal-aid Project Number: (if one has been assigned)
Project Description:
Project Location:
Subject: (*Source Inspection for Project Name, County*)

We are requesting that Caltrans provide Source Inspection (reimbursed) services for the above mentioned project. We understand we are responsible for paying for this service provided for by the State. Listed below are the materials for which we are requesting Caltrans' Source Inspection (reimbursed) services.

Materials that will require source inspection:

Justification for request: (Based on the requirements in Section 16.14 under "Source Inspection") _____

Any question you might have about the above materials should be directed
to: _____, at (phone #) .

Approved:

(Applicant Representative Name)

District Local Assistance Engineer

(Title)

(Date)

(Local agency, name & address)

Attachment #2



Appendix F - Construction Materials Accepted by a Certificate of Compliance *

Soil Amendment
Fiber
Mulch
Stabilizing Emulsion
Plastic Pipe
Lime
Reinforcing Steel
Structural Timber and Lumber
Treated Timber and Lumber
Timber and Lumber
Culvert and Drainage Pipe Joints
Reinforced Concrete Pipe
Corrugated Steel Pipe and Corrugated Steel Pipe Arches
Structural Metal Plate Pipe Arches and Pipe Arches
Perforated Steel Pipe
Polyvinyl Chloride Pipe and Polyethylene Tubing
Steel Entrance Tapers, Pipe Down drains, Reducers, Coupling Bands and Slip Joints
Aluminum Pipe (Entrance Tapers, Arches, Pipe Down drains, Reducers, Coupling Bands and Slip Joints)
Metal Target Plates
Electrical Conductors
Portland Cement
Minor Concrete
Waterstop

* If Caltrans Standard Specifications May 2006 is part of contract specifications.

Note: Usually these items are inspected at the site of manufacture or fabrication and reinspected after delivery to the job site.



Appendix J.1 - Example of a Vendor's Certificate of Compliance

No. 583408

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
VENDOR'S CERTIFICATE OF COMPLIANCE
MR-0543 (REV. 5/93) #CT-7541-6020-2

☐ PRECAST CONCRETE PRODUCTS OR ☒ SOUNDWALL

TO: BILL SYNDER

STATE HIGHWAY ENGINEER
RESIDENT ENGINEER - CITY OF FLATLAND

We certify that the portland cement, chemical and mineral admixtures contained in the material described below are brands stated and comply with specifications for:

CONTRACT NUMBER:

CEMENT BRAND

XYZ CEMENT CO.

TYPE

II MODIFIED

MILL LOCATION

MIDLAND,
CALIFORNIA

CHEMICAL ADMIXTURE

1. BRAND

ABC ADMIXTURE

TYPE

WATER REDUCER

MANUFACTURER

XYZ SUPPLIER

2. BRAND

TYPE

MANUFACTURER

☐ CHECK BOX IF A CHEMICAL ADMIXTURE WAS NOT USED

MINERAL ADMIXTURE

MANUFACTURER

POZZ. INC.

CLASS

F

☐ CHECK BOX IF A MINERAL ADMIXTURE WAS NOT USED

DELIVERY DATE (Ready-Mix)

7/7/07

DATES OF FABRICATION (Precast)

LIST PRODUCTS TO WHICH CERTIFICATE APPLIES. (Show size and len. ft. of pipe, etc., delivery slip numbers for ready-mix.)

Portland Cement
Flyash
Water Reducer

MANUFACTURER OF CONCRETE PRODUCTS

A.E.B. READY MIX

By: AUTHORIZED REPRESENTATIVE SIGNATURE

Joe Anderson

FW 93 (839)

Original to Res. Engr. Retain Duplicate.

OSP 01 55624



Appendix J.2 - Example of a Certificate of Compliance for Portland Cement (continued)

This is to certify that the

Portland Cement

Supplied by ABC Cement Company complies with all
requirements for Type II Portland Cement when tested in
accordance with ASTM C - 494.

Local Agency Project No.

HP21L - 5055 - 111

Albert Howakowa

Quality Assurance Engineer
ABC Cement Company

Date: 07/07/07



Appendix K - Examples of Materials Certificates/Exceptions (Signed by the Resident Engineer at the Completion of the Project)

Federal-aid Project No.: Project HP21L -- 5055 -- 111

Subject: Materials Certification

This is to certify that the results of the tests on acceptance samples indicate that the materials incorporated in the construction work and the construction operations controlled by sampling



and testing were in conformity with the approved plans and specifications.



All materials exceptions to the plans and specifications on this project are noted below.

No exceptions were found to the plans and specifications on this project.

Bill Sanders
Resident Engineer (Print Name)

Bill Sanders
Resident Engineer (Signature)

7/7/07
(Date)

Note: The signed original of this certificate is placed in the Resident Engineer's project files and one copy is mailed to the DLAE and filed under "Report of Expenditures."

See the attachment (next page)



Appendix K (continued)

Attachments: Materials Exceptions (Acceptance Testing)

Type of Test	Description of Work	Total Tests Performed On the Project	Number of Failed Tests	Action Taken
Slump Test	Concrete Sidewalk	8	1	When the measured slump exceeded the maximum limit, the entire concrete load was rejected.
Sand Equivalent	Aggregate for Structural Concrete	10	1	The tested S.E. was 70 and the contract compliance specification was 71 minimum. However, the concrete 28-day compressive strength was 4800 psi. The concrete was considered adequate and no materials deductions were taken.
Compaction	Sub grade Material	12	1	One failed test was noted. The failed area was watered and reworked. When this was completed, a retest was performed. The retest was acceptable.
Compaction	Hot Mix Asphalt	12	1	One failed area was noted. It was reworked and retested. The second test met specifications.

Bill Sanders

Resident Engineer (Print Name)

Bill Sanders

Resident Engineer (Signature)

July 4, 2007

Date



Appendix H - Example of a Log Summary Sheet

Subgrade Materials

Date	CT	Station	Elevation	Test Results	Minimum Spec.	Passed or Failed	Action Taken
5/15/07	231	1+ 00 (30' L)	99.00	93	90 or greater	Passed	N/A
5/16/07	231	1+ 50 (20' R)	100.50	94	90 or greater	Passed	N/A
5/17/07	231	2+ 25 (25' R)	101.00	96	90 or greater	Passed	N/A
5/18/07	231	1+ 50 (30' L)	101.50	95	95 or greater	Passed	N/A
5/19/07	231	2+ 50 (20' L)	102.00	92 *	95 or greater	Failed	See Note 1
5/19/07	231	2+ 50 (20' L)	102.00	95	95 or greater	Passed	N/A

CT 231 = Compaction (Nuclear Gage)

* Note 1: The Contractor used a water tank to dampen the soil surface at the failed subgrade location. Using a sheep's foot compactor, he reworked the subgrade (making at least 10 passes) from Station 2+ 00 to Station 3+ 00. After approximately 30 minutes, another compaction test was taken. This time the relative compaction was 95.

Aggregates and Base Materials

Date	CT	Station	Elevation	Test Results	Minimum Spec.	Passed or Failed	Action Taken
6/20/07	202	1+ 00 (10' R)	102.50	See data sheet	See data sheet	Passed	N/A
6/20/07	202	2+ 00 (20' L)	102.50	See data sheet	See data sheet	Passed	N/A
6/22/07	217	1+ 00 (10' R)	102.50	75	25 or greater	Passed	N/A
6/22/07	217	2+ 00 (20' L)	102.50	83	25 or greater	Passed	N/A
6/20/07	227	1+ 00 (20' R)	102.50	86	71 or greater	Passed	N/A
6/20/07	227	1+ 50 (20' L)	102.50	85	71 or greater	Passed	N/A
6/24/07	231	2+ 00 (20' R)	102.50	98	95 or greater	Passed	N/A
6/24/07	231	2+ 50 (20' L)	102.50	97	95 or greater	Passed	N/A

CT 202 = Sieve Analysis, CT 217 = Sand Equivalent, CT 227 = Cleaness Value,
CT 231 = Compaction (Nuclear Gage)



Appendix H (continued)

Hot Mix Asphalt

Date	CT	Station	Elevation	Test Results	Minimum Spec.	Passed or Failed	Action Taken
7/10/07	339	1+ 00 (10' R)	103.00	0.08 gal/ sq yd	0.05 -0.10 gal/sq yd	Passed	N/A
7/10/07	366	2+ 00 (20' L)	103.00	32	>23	Passed	N/A
7/10/07	366	1+ 00 (10' R)	103.00	41	>23	Passed	N/A
7/10/07	375	2+ 00 (20' L)	103.00	94	RC = 93 to 97	Passed	N/A
7/15/07	375	1+ 00 (20' R)	103.00	96	RC = 93 to 97	Passed	N/A
7/15/07	375	1+ 50 (20' L)	103.00	95	RC = 93 to 97	Passed	N/A

CT 339 = Distributor Spread Rate, CT 366 = Stabilometer Value
CT 375 = In-Place Density & Relative Compaction

Portland Cement Concrete

Date	CT	Station	Elevation	Test Results	Minimum Spec.	Passed or Failed	Action Taken
9/25/07	504	10 + 50 (50' R)	102.50	6.5%	>6.0%	Passed	N/A
9/25/07	533	12 + 50 (50' R)	102.50	1.5"	<2"	Passed	N/A
9/25/07	518	11 + 50 (50' R)	102.50	151 lb/cu ft	> 145 lb/cu ft	Passed	N/A
9/25/07	521	10 + 50 (50' R)	102.50	28 day = 4200 psi	>3800 psi	Passed	N/A
9/28/07	521	11 + 50 (50' R)	102.50	28 day = 4290 psi	>3800 psi	Passed	N/A
9/30/07	521	12 + 50 (50' R)	102.50	28 day = 4160 psi	>3800 psi	Passed	N/A

CT 504 = Air Content, CT 518 = Unit Weight, CT 521 = Compressive Strength,
CT 533 = Ball Penetration